

TABLE 4 TO SUBPART KKKKK OF PART 63.—REQUIREMENTS FOR PERFORMANCE TESTS—Continued

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
4. Kiln equipped with a DIFF or DLS/FF	b. Establish the operating limit for the limestone feeder setting.	Data from the limestone feeder during the performance test.	You must ensure that you maintain an adequate amount of limestone in the limestone hopper, storage bin (located at the top of the DLA), and DLA at all times during the performance test. You must establish your limestone feeder setting one week prior to the performance test and maintain the feeder setting for the one-week period that precedes the performance test and during the performance test.
	c. Document the source and grade of limestone used. Establish the operating limit for the lime feeder setting.	Records of limestone purchase. Data from the lime feeder during the performance test.	For continuous lime injection systems, you must ensure that lime in the feed hopper or silo and to the APCD is free-flowing at all times during the performance test and record the feeder setting for the three test runs. If the feed rate setting varies during the three test runs, determine and record the average feed rate from the three test runs.
5. Kiln equipped with a WS	a. Establish the operating limit for the average scrubber pressure drop.	Data from the pressure drop measurement device during the performance test.	You must continuously measure the scrubber pressure drop, determine and record the block average pressure drop values for the three test runs, and determine and record the 3-hour block average of the recorded pressure drop measurements for the three test runs.
	b. Establish the operating limit for the average scrubber liquid pH.	Data from the pH measurement device during the performance test.	You must continuously measure the scrubber liquid pH, determine and record the block average pH values for the three test runs, and determine and record the 3-hour block average of the recorded pH measurements for the three test runs.
	c. Establish the operating limit for the average scrubber liquid flow rate.	Data from the flow rate measurement device during the performance test.	You must continuously measure the scrubber liquid flow rate, determine and record the block average flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded flow rate measurements for the three test runs.
6. Kiln equipped with a WS that includes chemical addition to the water.	Establish the operating limit for the average scrubber chemical feed rate.	Data from the chemical feed rate measurement device during the performance test.	You must continuously measure the scrubber chemical feed rate, determine and record the block average chemical feed rate values for the three test runs, and determine and record the 3-hour block average of the recorded chemical feed rate measurements for the three test runs.

As stated in § 63.8605, you must demonstrate initial compliance with each emission limitation that applies to you according to the following table: