

Table E.II.3

Preventative & Mitigative Measures addressing Time Dependent and Independent Threats for Transmission Pipelines that Operate Below 30% SMYS, in HCAs

3 rd Party Damage	103-(Gen. Design)	615 -(Emerg Plan)	<ul style="list-style-type: none"> • Participation in state one-call system, • Use of qualified operator employees and contractors to perform marking and locating of buried structures and in direct supervision of excavation work, AND • Either monitoring of excavations near operator's transmission pipelines, or bi-monthly patrol of transmission pipelines in HCAs or class 3 and 4 locations. Any indications of unreported construction activity would require a follow up investigation to determine if mechanical damage occurred.
	111-(Design factor)		
	317-(Hazard prot)		
	327-(Cover)		
	614-(Dam. Prevent)		
	616-(Public educat)		
	705-(Patrol)		
	707-(Line markers)		
	711 (Repair – gen.)		
	717-(Repair – perm.)		