

If you want a departure to:	Then you must...
(a) Use flexible hose for diverter lines instead of rigid pipe. (b) Use only one spool outlet for your diverter system. (c) Use a spool with an outlet with an internal diameter of less than 10 inches on a surface wellhead. (d) Use a single diverter line for floating drilling operations on a dynamically positioned drillship.	Use flexible hose that has integral end couplings. (1) Have branch lines that meet the minimum internal diameter requirements; and (2) Provide downwind diversion capability. Use a spool that has dual outlets with an internal diameter of at least 8 inches. Maintain an appropriate vessel heading to provide for downwind diversion.

§ 250.433 What are the diverter actuation and testing requirements?

When you install the diverter system, you must actuate the diverter sealing element, diverter valves, and diverter-control systems and control stations. You must also flow-test the vent lines.

(a) For drilling operations with a surface wellhead configuration, you must actuate the diverter system at least once every 24-hour period after the initial test. After you have nipped up on conductor casing, you must pressure-test the diverter-sealing element and diverter valves to a minimum of 200 psi. While the diverter is installed, you must conduct subsequent pressure tests within 7 days after the previous test.

(b) For floating drilling operations with a subsea BOP stack, you must actuate the diverter system within 7 days after the previous actuation.

(c) You must alternate actuations and tests between control stations.

§ 250.434 What are the recordkeeping requirements for diverter actuations and tests?

You must record the time, date, and results of all diverter actuations and tests in the driller's report. In addition, you must:

- (a) Record the diverter pressure test on a pressure chart;
- (b) Require your onsite representative to sign and date the pressure test chart;
- (c) Identify the control station used during the test or actuation;
- (d) Identify problems or irregularities observed during the testing or actuations and record actions taken to remedy the problems or irregularities; and
- (e) Retain all pressure charts and reports pertaining to the diverter tests and actuations at the facility for the duration of drilling the well.

Blowout Preventer (BOP) System Requirements

§ 250.440 What are the general requirements for BOP systems and system components?

You must design, install, maintain, test, and use the BOP system and system components to ensure well control. The working-pressure rating of each BOP

component must exceed maximum anticipated surface pressures. The BOP system includes the BOP stack and associated BOP systems and equipment.

§ 250.441 What are the requirements for a surface BOP stack?

(a) When you drill with a surface BOP stack, you must install the BOP system before drilling below surface casing. The surface BOP stack must include at least four remote-controlled, hydraulically operated BOPs, consisting of an annular BOP, two BOPs equipped with pipe rams, and one BOP equipped with blind or blind-shear rams.

(b) No later than February 21, 2006, your surface BOP stack must include at least four remote-controlled, hydraulically operated BOPs consisting of an annular BOP, two BOPs equipped with pipe rams, and one BOP equipped with blind-shear rams. The blind-shear rams must be capable of shearing the drill pipe that is in the hole.

(c) You must install an accumulator system that provides 1.5 times the volume of fluid capacity necessary to close and hold closed all BOP components. The system must perform with a minimum pressure of 200 psi above the precharge pressure without assistance from a charging system. If you supply the accumulator regulators by rig air and do not have a secondary source of pneumatic supply, you must equip the regulators with manual overrides or other devices to ensure capability of hydraulic operations if rig air is lost.

(d) In addition to the stack and accumulator system, you must install the associated BOP systems and equipment required by the regulations in this subpart.

§ 250.442 What are the requirements for a subsea BOP stack?

(a) When you drill with a subsea BOP stack, you must install the BOP system before drilling below surface casing. The District Supervisor may require you to install a subsea BOP system before drilling below the conductor casing if proposed casing setting depths or local geology indicate the need.

(b) Your subsea BOP stack must include at least four remote-controlled, hydraulically operated BOPs consisting of an annular BOP, two BOPs equipped with pipe rams, and one BOP equipped with blind-shear rams.

(c) You must install an accumulator closing system to provide fast closure of the BOP components and to operate all critical functions in case of a loss of the power fluid connection to the surface. The accumulator system must meet or exceed the provisions of Section 13.3, Accumulator Volumetric Capacity, in API RP 53, Recommended Practices for Blowout Prevention Equipment Systems for Drilling Wells (incorporated by reference as specified in § 250.198). The District Supervisor may approve a suitable alternative method.

(d) The BOP system must include an operable dual-pod control system to ensure proper and independent operation of the BOP system.

(e) Before removing the marine riser, you must displace the riser with seawater. You must maintain sufficient hydrostatic pressure or take other suitable precautions to compensate for the reduction in pressure and to maintain a safe and controlled well condition.

§ 250.443 What associated systems and related equipment must all BOP systems include?

All BOP systems must include the following associated systems and related equipment:

(a) An automatic backup to the primary accumulator-charging system. The power source must be independent from the power source for the primary accumulator-charging system. The independent power source must possess sufficient capability to close and hold closed all BOP components.

(b) At least two BOP control stations. One station must be on the drilling floor. You must locate the other station in a readily accessible location away from the drilling floor.

(c) Side outlets on the BOP stack for separate kill and choke lines. If your stack does not have side outlets, you must install a drilling spool with side outlets.